

Licence Specific Conditions

1. Appropriately graded, sized and designed loose rock armour shall be used in place of the Reno Mattress at diffuser.
2. The outfall pipe shall be buried a minimum of 0.5m below existing bed over its entire length.
3. The diffuser shall be constructed and maintained so as to not impact upon navigation.
4. All works shall be carried out in accordance with Drawing Titled: Foreshore Licence Map Sheet 2 of 2, Drawing No: 07 Rev., Date: 05/12/2013 and Drawing Titled: Outfall and Diffuser, Drawing. No: 13524-C-008 Rev: B. Date 27/09/2013.