

**AN ROINN TALMHAÍOCHTA, BIA AGUS MARA
DEPARTMENT OF AGRICULTURE, FOOD AND THE MARINE**

**ACCEPTED PRE-CAST WALL PANELS AND A-SEGMENT WALLS FOR
USE IN GRAIN STORES**

This list details all the companies that are accepted as producing pre-cast wall panels that are eligible for use as Load Bearing Wall Panels or A-segment walls (bunker walls) for use in Grain Stores that are being grant-aided. Pre-cast wall panels or A-segment walls (bunker walls) supplied by manufacturers not on this list cannot be grant aided.

If a pre-cast wall panel or A-segment walls (bunker walls) manufacturing company which is not on this list wishes to be included, they should contact: Engineering Unit, Nitrates, Biodiversity and Engineering Division, Pavilion A, Grattan Business Centre, Dublin Road, Portlaoise, Co. Laois.

Table 1: Accepted precast Load bearing wall panels

Name	Address	Length (m)	Height (m)	Thickness (m)
Neeppoc Ltd t/a Alfabloc Walling Systems,	Coppeen, Enniskeane, Co. Cork	Up to 4.9m	1.2	150

Load bearing precast wall panels shall be supported in accordance with manufacturers' instructions. The wall panels may be fixed either between stanchions or to either the inside or outside of the stanchions.

Table 2: Accepted precast A-segment walls (bunker walls)

Name	Address	Height (m)	Length (m)	Base width (m)
Moore Concrete Products Limited	Caherty House, 41 Woodside Road, Ballymena, Co. Antrim BT42 4QH Northern Ireland	4.3	1.2	0.710
		4.0	1.2	0.960
		3.6	1.2	1.130
		3.0	1.2	1.130
		2.4	1.2	1.130
		1.5	1.2	1.130
John Murphy Concrete Ltd., t/a Murphy Concrete Products	Four Winds, Curragraigue, Enniscorthy, Co Wexford.	3.0	1.2	1.3
Neeppoc Ltd t/a Alfabloc Walling Systems,	Coppeen, Enniskeane, Co. Cork	3.05	1.22	1.22
		2.4	1.22	0.762
Spillane Pre Cast Concrete Ltd	Cunnahurt, Nenagh, Co. Tipperary	2.4	1.2	1.5
		3.0	1.2	1.5